

Noah Kanwal, Owner

727-902-1986

paintnpete@gmail.com

www.paintnpete.com

1105 18th St S, St. Petersburg, FL 33712

PREPARED FOR

Danielle

1047 37th Ave NE

St. Petersburg, FL 33704

+1 (410) 218-9578

PROJECT

Complete Exterior Repaint

Concrete block residence

Full seal · full prime · two-coat acrylic finish system

Metal entry pillars · doors · decorative statuary

① Scope of Work

The following describes the complete exterior coating system proposed for the residence at 1047 37th Ave NE. All work is performed to manufacturer specification using premium materials chosen for Florida's coastal heat, humidity, and UV exposure — because preparation is what makes a finish last.

Surface Preparation & Cleaning

All exterior surfaces to be coated are cleaned to remove chalking, mildew, dirt, and loose material, then allowed to dry fully prior to sealing and priming. Landscaping, hardscape, glass, and fixtures are masked and protected throughout the project.

Window Perimeter Re-Seal

Full re-seal at all window corners. Existing failed or aged sealant is cut out and removed; joints are cleaned and re-sealed with a high-quality exterior-grade elastomeric sealant, tooled to a clean, watertight profile. This is the primary defense against water intrusion on a block home.

Crack Sealing — Concrete

Miscellaneous light crack sealing throughout the concrete substrate. Hairline and minor cracks are opened as needed, cleaned, filled with an appropriate patching or sealant material, then feathered smooth so the repair disappears beneath the finish coats.

Full Prime Coat

A complete prime coat is applied to all surfaces to be painted — not a spot prime. Priming the entire substrate equalizes porosity across patched and unpatched concrete, blocks alkalinity, and gives the finish coats a uniform surface to bond to.

Finish Coats — Face Walls, Soffits & Trim

Two (2) full coats of premium 100% acrylic latex in Duration grade or higher, applied to all face walls, soffits, and trim. Colors and sheens are the client's selection. Two full coats over a full prime deliver true color depth, uniform sheen, and the film build required for long-term performance in this climate.

Front Entry Metal Pillars

Metal support pillars at the front entrance are prepared and recoated with **Pro-Cryl universal primer**, followed by a **DTM (direct-to-metal) acrylic finish**. Color is the client's choice. This system is specified for corrosion resistance and adhesion on metal, where standard wall paint will not hold up.

Exterior Doors — Three (3)

Three exterior doors prepared and finished, including edges and the visible door face. Hardware is removed or masked as appropriate and reinstalled on completion.

Decorative Horse Statues — Two (2)

Two decorative horse statues at the front entryway are cleaned, prepared, and finished by hand. These are detail pieces and are treated as such — brushwork, careful masking, and a finish built for continuous outdoor exposure.

Cleanup & Final Walkthrough

All masking and protection removed, work areas returned to their original condition, and debris hauled off daily. The project closes with a walkthrough together so every elevation is reviewed and approved before final invoicing.

2

Investment Summary

DESCRIPTION	QTY	RATE	AMOUNT
Complete Exterior Coating System Surface preparation and cleaning · full re-seal at all window corners · miscellaneous light crack sealing · full prime coat · two coats premium acrylic latex (Duration grade or higher) on all face walls, soffits and trim · metal entry pillars recoated with Pro-Cryl primer and DTM finish. Includes all labor, materials, masking, protection and cleanup.	1	\$4,838.40	\$4,838.40
Exterior Doors — Prepared & Finished Three (3) exterior doors, including edges and visible faces; hardware removed or masked and reinstalled.	3	\$250.00	\$750.00
Decorative Horse Statues — Hand Finished Two (2) statues at the front entryway; cleaned, prepared, and hand finished for continuous exterior exposure.	2	\$250.00	\$500.00
Subtotal			\$6,088.40
Adjustments			\$0.00
PROJECT TOTAL			\$6,088.40

Deposit due at scheduling (50%): **\$3,044.20**

Balance due upon completion: **\$3,044.20**

All-inclusive pricing. The figure above covers labor, all materials and coatings, masking and protection of surrounding surfaces, equipment, and daily cleanup. There are no separate material charges and no hidden line items. Colors and sheens are the client's selection at no additional cost.

3

Materials & Specifications

Joint Sealant	Exterior-grade elastomeric sealant at all window corners and perimeters, tooled and finished for a watertight joint.
Patching Compound	Exterior masonry patching and crack filler, feathered flush to the surrounding concrete.
Primer — Masonry	Full-coverage exterior masonry primer over all painted surfaces; alkali resistant and formulated for concrete block.
Finish — Walls, Soffits & Trim	Sherwin-Williams Duration Exterior Acrylic Latex (or higher grade), two full coats. Sheen by client selection.
Primer — Metal	Sherwin-Williams Pro-Cryl Universal Primer on all prepared metal at the front entry pillars.
Finish — Metal	DTM (direct-to-metal) acrylic finish over Pro-Cryl. Color by client selection.
Substitutions	Any product substitution will be equal or better in grade and will be reviewed with the client in writing before use.

④ Color Selections

Colors and sheens are entirely your choice and carry no additional cost. Use the space below to record your selections — finalizing these before the start date keeps the schedule clean.

SURFACE	COLOR / MANUFACTURER CODE	SHEEN
Face Walls		
Soffits		
Trim		
Exterior Doors (3)		
Metal Entry Pillars (DTM)		
Horse Statues (2)		

⑤ Terms & Conditions

- **Validity.** This estimate is valid for thirty (30) days from the date issued — through September 16, 2026.
- **Payment.** A 50% deposit is due at scheduling to reserve the crew and order materials; the remaining 50% is due upon completion and client walkthrough.
- **Scheduling.** A start date is confirmed once the deposit is received. Exterior work is weather dependent; rain or excessive humidity may shift the schedule, and you will be notified promptly of any change.
- **Changes in scope.** Any additional work is documented in a written change order and approved by the client before it begins.
- **Warranty.** All workmanship is warranted for two (2) years from completion against peeling, blistering, and flaking attributable to application. Manufacturer coating warranties apply in addition and pass through to the homeowner.
- **Not included.** Structural or stucco reconstruction, wood rot replacement, pressure-washing of driveways or walkways, and remediation of pre-existing water intrusion.
- **Site access.** Client to provide access to all exterior elevations, water, and standard exterior power.
- **Insurance.** Paint'n Pete carries general liability coverage; a certificate is available on request.

Acceptance of Estimate

By signing below, the client accepts the scope of work, pricing, and terms described in this estimate and authorizes Paint'n Pete to schedule and perform the work as specified. This document becomes the working agreement between both parties upon signature.

CLIENT SIGNATURE —
DANIELLE

8/16/2026
DATE


NOAH KANWAL — PAINT'N PETE

Thank you for the opportunity to bid this project, Danielle. If you'd like to walk through any line item or adjust the scope, call or text me directly at **727-902-1986** — I'm glad to talk it through.